



Public Works Commission Special Meeting



April 18, 2018




WTP Testing Summary

- Conducted bench- and pilot-scale testing for treatment of sand, iron sulfide, hydrogen sulfide, iron, manganese, and arsenic
- Hollywood wells (2, 4, 5, and 6) and Maple wells (1 and 2)
- Draft pilot report submitted by Carollo, under staff review



WTP Testing Process Flow





Raw Water Blowdown

- Remove particles within the well raw water pipelines upon well start-up
- Flush out constituents with large chlorine demand





Sand Separator

- Capture particles such as iron sulfide and sand, which wells produce during operation
- Reduce particle loading to RO process, prevent membrane fouling and differential pressure shutdown





Oxidation/Media Filtration

- Remove iron sulfide, hydrogen sulfide, iron, manganese, and arsenic
- Stabilize raw water and provide RO with particle-free water





Next Steps

- City staff to review draft report submitted by Carollo and provide findings to PWC in May
 - Executive Summary
 - Testing Background, Methodology, and Results
 - Proposed Design
 - Project Delivery Methods
 - Cost and Schedule
 - Recommendations



Any Questions

